

**कार्यालय निदेशक एवं मुख्य अभियन्ता, ग्रामीण अभियन्त्रण सेवा, उत्तर प्रदेश लखनऊ।**

पत्रांक-<sup>543</sup> / ग्रा0अ0से0 / प्रगति विवरण / 2010-11 / दिनांक - 21 नवम्बर , 2010

विषय:- भौतिक प्रगति का प्रतिशत निर्धारण के सम्बन्ध में।

1. समस्त अधिशासी अभियन्ता,  
ग्रामीण अभियन्त्रण सेवा,  
उत्तर प्रदेश, लखनऊ।
2. समस्त अधीक्षण अभियन्ता,  
ग्रामीण अभियन्त्रण सेवा,  
उत्तर प्रदेश, लखनऊ।

कृपया इस कार्यालय के पत्र सं0-184 / ग्रा0अ0से0 / मा0 / प्रगति समीक्षा / 10-11, दिनांक 11.06.2010 का सन्दर्भ ग्रहण करें, जिसके द्वारा सामान्य योजनाओं के अन्तर्गत निष्पादित कराये जा रहे कार्यों की गुणवत्ता एवं समयबद्ध ढंग से पूर्ण कराने हेतु कार्यवार पर्यवेक्षण करने के उद्देश्य से वित्तीय/भौतिक प्रगति प्रारूप संलग्न कर भेजे गये हैं। उक्त सन्दर्भित पत्र के माध्यम से प्रेषित रूप पत्रों की भौतिक प्रगति को एकरूपता रखने हेतु भवन एवं मार्गों का प्रतिशत संलग्न विवरण के अनुसार निर्धारित किया जाता है।

अतः आप कृपया अपने प्रखण्ड/परिमण्डल के अन्तर्गत निष्पादित कराये जा रहे निर्माण कार्यों की वित्तीय प्रगति के साथ ही भौतिक प्रगति का निर्धारण संलग्न विवरण के अनुसार आगामी प्रगति रिपोर्ट में प्रतिशत का अंकन आवश्यक सुनिश्चित किया जाए।

(उमाशंकर)

निदेशक एवं मुख्य अभियन्ता

पत्रांक एवं दिनांक उपरोक्तानुसार।

प्रतिलिपि मुख्य अभियन्ता (पूर्वी/पश्चिमी), ग्रामीण अभियन्त्रण सेवा, उत्तर प्रदेश, लखनऊ को उक्त प्रतिशत निर्धारण सम्बन्धी विवरण की एक प्रति सहित सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

(उमाशंकर)

निदेशक एवं मुख्य अभियन्ता

निदेशालय के पत्रांक 543 / ग्रा0अ0से0/मा0/प्रगति रिपोर्ट/10-11, दिनांक 29.11.10  
भौतिक प्रगति का निर्धारण सम्बन्धी विवरण।

द्वारा प्रेषित

**Reporting of Physical Progress under general, schemes**

	Value	Cumulative
<b>Building works:-</b>		
<b>A- Single Storey Building</b>		
1- Work Completed up to DPC Level	20%	20%
2- Work Completed up to Slab Level	30%	50%
3- Work Completed up Plasiring, Sanitary, Electrification, flooring, etc	25%	75%
4- Work Completed in all aspects	25%	100%
<b>B- Double Storey Building</b>		
1- Work Completed up to DPC Level	15%	15%
2- Work Completed up to First Slab Level	20%	35%
3- Work Completed up to Second Slab Level	20%	55%
4- Work Completed up Plastering, Sanitary, Electrification, flooring, etc	20%	75%
5- Work Completed in all aspects	25%	100%
<b>C- Triple Storey Building</b>		
1- Work Completed up to DPC Level	10%	10%
2- Work Completed up to First Slab Level	15%	25%
3- Work Completed up to Second Slab Level	15%	40%
4- Work Completed up to Third Slab Level	15%	55%
5- Work Completed up Plastering, Sanitary, Electrification, flooring, etc	20%	75%
6- Work Completed in color wash, side development and all aspects	25%	100%
<b>Road Works:-</b>		
<b>A- Road work sanctioned up to Earth work level and CD Structures</b>		
1- Work Completed up to Earth work	50%	50%
2- CD Structure completed	50%	100%
<b>B- Road work sanctioned up to Kharanja level and CD Structures</b>		
1- Work Completed up to Earth work	30%	30%
2- CD Structure completed	30%	60%
3- Kharanja work completed	40%	100%
<b>C- Road work sanctioned up to Painting level and CD Structures</b>		
1- Work Completed up to Earth work	20%	20%
2- CD Structure completed	15%	35%
3- G-1/GSB work completed	15%	50%
4- G-2 work completed	15%	65%
5- G-3 work completed	15%	80%
6- BT work with Finishing in all aspects completed	20%	100%
<b>D- Road work sanctioned for up-gradation</b>		
1- Work Completed up to Earth work	10%	10%
2- CD Structure completed	10%	20%
3- G-1/GSB work completed	15%	35%
4- G-2 work completed	15%	50%
5- G-3 work completed	20%	70%
6- BT work with Finishing in all aspects completed	30%	100%

352

29/11/2010

The Physical Progress of every work will be worked out on the basis of relevant percentage weighted in terms of the length of the road. For example, If a road under construction is having a length of 7 Km and the Physical Progress is as given below, the evaluation of Physical Progress will be made as shown below.

Item	Progress in terms of completed length	Calculation of percentage progress	Percentage Progress (Approximate)
Earth work	5 Km	$5/7 * 20\%$	14.0%
CD	50 % CD is complete	$50\% * 15\%$	7.50%
Sub-base G-1/GSB	5 Km	$5/7 * 15\%$	10.70%
Base course G-2	4 Km	$4/7 * 15\%$	8.60%
Base course G-3	3 Km	$3/7 * 15\%$	6.40%
BT work with Finishing in all aspects completed	2 Km	$2/7 * 20\%$	5.70%
<b>Total Progress</b>			<b>52.9%</b>

Physical Progress of the entire District will be the average of the Percentage (Weighed on the basis of road length) Physical Progress of all the roads in that District; similarly, the Physical Progress of entire State will be the average of Percentage Physical Progress of all the Districts.

2022-23  
BE (P)

(उमाशंकर)  
निदेशक एवं मुख्य अभियन्ता